

CP-3

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
7-5-1962
JUL 5 1962

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Morganstern - Specter
Complete Address: Box 661 Russell, Kansas
Lease Name Roy Martin Well No. 3
Location NE SE NW Sec. 9 Twp. 10 Rge. (E) (W) 21
County Graham Total Depth 3873
Abandoned Oil Well x Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Ralph Lynch
Address: Great Bend, Kansas License No. 457
Operation Completed: Hour 5PM Day 3 Month 7 Year 62

The Above well was plugged as follows:

8 5/8" 322' circulated with cement - 5 1/2" 3870' with 175 sax cement PB 3824'
Perf - Staging collar at 3227' - 5 1/2" circulated with Oily gel mud.
Filled hole with sand to 3300', set 4 sax cement with dump bailer - pulled
3090' 5 1/2" to 550', circulated hole with heavy gel mud through 5 1/2" at 550',
displaced 20 sax cement through 5 1/2" at 550', heavy mud to 180', displaced
20 sax cement through 5 1/2" at 180', heavy mud to 35', set bridge and filled
to bottom cellar with cement.

Mudding and cementing by Lynch Company Pump Truck.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE

7-6-62

INV. NO.

5312-W

Signed:

Well Plugging Supervisor