

CP-3

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
7-9-1962
JUL 9 1962
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Morganstern - Specter
Complete Address: ~~Ruby Martin~~ Box 661 Russell, Kansas
Lease Name Ruby Martin Well No. 1
Location NW NW NE Sec. 9 Twp. 10 Rge. (E) (W) 21
County Graham Total Depth 3884
Abandoned Oil Well x Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Knight Casing Pulling
Address: Chase, Kansas License No. 436
Operation Completed: Hour 6PM Day 6 Month 7 Year 62

The Above well was plugged as follows:

8 5/8" 317' circulated with cement - 5 1/2" 3869' with 150 sax cement DV tool
3258' circulated hole with oily mud 3258' to 0' - PB 3645' - perf 3621'
5 1/2" squeezed in Dakota section with 100 sax cement.
Sanded back to 3300', set 4 sax cement with dump bailer, pulled 1022' 5 1/2"
to 425', circulated hole with heavy gel mud through 5 1/2" - displaced 20 sax
cement through 5 1/2" at 425', heavy mud to 180', displaced 20 sax cement
through 5 1/2" at 180', heavy mud to 35', set bridge and filled to bottom
cellar with cement.

Mudding and cementing by Knight Company pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/9/62

INV. NO. 5332-W

Signed: [Signature]
Well Plugging Supervisor