

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Okmar Oil Company,
Complete Address 1130 Vickers KSB&T Building, Wichita, Kansas.
Lease Name Martin Webster Well No. 2
Location CS/2-SW-NE Sec. 9 Twp. 10 Rge. (E) (W) 21
County Graham Total Depth 3867'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Southwest Casing Pulling Company, Incorporated,
Address Box #364, Great Bend, Kansas. License No. 399
Operation Completed: Hour 5:45 PM Day 30 Month 6 Year 1970

The above well was plugged as follows:

107'--8 5/8" Surface casing, cement circulated with 60 Sx.
3863'--5 1/2" Production casing, cemented on bottom with 150 Sx. 5 1/2" has been squeezed
@ 1400' with 250 Sx. cement.

Sanded well back to 3850' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
(Recovered 1440' 5 1/2") and squeezed well initially with 3 sacks hulls and followed with
60 Sx. cement then 6 sacks gel and finally 70 Sx. cement to bottom of cellar. Maxi-
mum pump-in pressure-500#. Final shut-in pressure-200#. (Mudding and cementing by
Halliburton. Checked top of cement in hole 7/1/70 and found it 3' below bottom of
cellar.

RECEIVED

I hereby certify that the above well was plugged as herein stated.

INVOICED

JUL 6 1970
7-6-1970
CONSERVATION DIVISION
Wichita, Kansas

Signed:

Well Plugging Supervisor

DATE 7/6/70INV. NO. 2169-W