

CP-3

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
7-5-1962  
JUL 5 1962

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Morganstern - Specter

Complete Address: Box 661 Russell, Kansas

Lease Name Ruby Martin Well No. 2

Location SW NW NE Sec. 9 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3854

Abandoned Oil Well x Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co

Address: Chase, Kansas License No. 436

Operation Completed: Hour 7PM Day 29 Month 6 Year 62

The Above well was plugged as follows:

8 5/8" 271' circulated with cement - 5 1/2" 3850' with 180 sax cement.  
5 1/2" into at approx 1400', ran measuring line and found well sanded back to  
3350', set 4 sax cement at 3350' with dump bailer, pulled 1400' 5 1/2" to  
550', circulated hole with heavy mud through 5 1/2" (30 sax Gel), displaced  
20 sax cement through 5 1/2" at 550', heavy mud to 180', displaced 20 sax  
cement through 5 1/2" at 180', heavy mud to 35', set bridge and filled to  
bottom cellar with cement.

Mudding and cementing by Knight Company Pump Truck.

I hereby certify that the above well was plugged as herein stated.

DATE 7/5/62  
INV. NO. 5311-w

Signed: [Signature]  
Well Plugging Supervisor

INVOICED