

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
7-9-1962
JUL 9 1962
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Morganstern - Specter
Complete Address: Box 661 Russell, Kansas
Lease Name Ruby Martin Well No. 3
Location NW SW NE Sec. 9 Twp. 10 Rge. (E) (W) 21
County Graham Total Depth 3853
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated: _____
Plugging Contractor: Knight Casing Pulling
Address: Chase, Kansas License No. 436
Operation Completed: Hour 2PM Day 4 Month 7 Year 62

The Above well was plugged as follows:

8 5/8" 275' circulated with cement - 5 1/2" 3843' with 175 sax cement DV tool
3186' circulated 5 1/2" with oily gel - perf 3583'
Filled with sand to 3300', set 4 sax cement with dump bailer, pulled 2840'
5 1/2" to 550', circulated hole with heavy gel mud, displaced 20 sax cement
through 5 1/2" at 550', heavy mud to 180', displaced 20 sax cement through 5 1/2"
at 180', heavy mud to 35', set plug and filled to bottom cellar with cement.

Mudding and cementing by Knight Company pump truck

I hereby certify that **INVOICED** the above well was plugged as herein stated.

DATE 7/9/62
INV. NO. 5334-U

Signed: [Signature]
Well Plugging Supervisor