

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NW NW SE

SEC. 9 TWP. 10 RGE. 21 *w*

Dry Hole ~~\_\_\_\_\_~~ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Teall

Operator M. B. Armer *Drilling Co. Inc.* Address 710 Kern Bldg  
Wichita, Kans

Field \_\_\_\_\_ County Graham

Total Depth 3821 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 113' circulated with cement - 5 1/2" at 3821' with 100 sax  
cement behind. Lane Wells plugs to 3670' - top perforations at  
3528'.

Filled with chat to 3520', set 4 sax cement with dump bailer,  
pulled 200', 5 1/2", filled hole with mud to 200', set rock bridge  
and 15 sax cement, mud to 35', set rock and 10 sax cement to  
bottom cellar.

**PLUGGING**  
FILE SEC 9-10-420  
BOOK PAGE 144 LINE 59

*E. J. Teall*  
District Conservation Agent  
Date 2-9-52  
**RECEIVED**  
STATE CORPORATION COMMISSION  
FEB 16 1952  
CONSERVATION DIVISION  
Wichita, Kansas