

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
7-9-1962  
JUL 9 1962  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Morganstern - Specter  
Complete Address: Box 661 Russell, Kansas  
Lease Name Roy Martin Well No. 2  
Location SE NE NW Sec. 9 Twp. KO Rge. (E) (W) 21  
County Graham Total Depth 3869  
Abandoned Oil Well x Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated:       
Plugging Contractor: Ralph Lynch  
Address: Great Bend, Kans License No. 457  
Operation Completed: Hour 10AM Day 7 Month 7 Year 62

The Above well was plugged as follows:

8 5/8" 310' circulated with cement - 5 1/2" 3867' with 180 sax cement, DV collar  
3203' circulated 5 1/2" with oily mud - pipe squeezed in Dakota section with  
100 sax cement.  
Sand back to 3300', set 4 sax cement with dump bailer, pulled 1330' 5 1/2" to  
550', circulated hole with heavy gel mud through 5 1/2" at 550', displaced 20  
sax cement through 5 1/2" at 550', heavy mud to 180', displaced 20 sax cement  
through 5 1/2" at 180', heavy mud to 35', set bridge and filled to bottom  
cellar with cement.

Mudding and cementing by Lynch Company pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 7/9/62  
INV. NO. 5333-W

Signed: [Signature]  
Well Plugging Supervisor