

CP-3

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
7-5-1962
JUL 5 1962

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Morganstern - Specter

Complete Address: Box 661 Russell, Kansas

Lease Name Roy Martin Well No. 1

Location NE NE NW Sec. 9 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3862

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ralph Lynch

Address: Great Bend, Kansas License No. 457

Operation Completed: Hour 7PM Day 29 Month 6 Year 62

The Above well was plugged as follows:

~~8 5/8" 316' circulated with cement - 5 1/2" 3860' with 160 sax cement.
DV collar at 3257', circulated with oily mud from 3257' to 0' - PB to
3616' - filled with sand to 3300', set 4 sax cement with dump bailer,
pulled 3258' 5 1/2" to 550', circulated hole with heavy mud at 550' (14 sax Gel)
displaced 20 sax cement through 5 1/2" at 550', heavy mud to 180', displaced
20 sax cement through 5 1/2" at 180', heavy mud to 35', set bridge and
filled with cement to bottom cellar.~~

~~Mudding and cementing by Lynch Company pump truck.~~

INVOLCED

I hereby certify that the above well was plugged as herein stated.

DATE 7/5/62
INV. NO. 5310-W

Signed: [Signature]
Well Plugging Supervisor