

**KANSAS**

Form CP-3  
Rev. 6-4-68

**STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**

**RECEIVED**  
STATE CORPORATION COMMISSION  
3-23-1973  
MAR 23 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name John O. Farmer, Incorporated,

Complete Address 370 West Wichita Avenue, Russell, Kansas.

Lease Name Miller Well No. 1

Location NW-NW-NW Sec. 11 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3845'

Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated

Plugging Contractor Above

Address  License No.

Operation Completed: Hour 11:15 AM Day 19 Month 3 Year 1973

The above well was plugged as follows:

150'--8 5/8" Surface casing, cement circulated with 125 Sx.

3843'--5 1/2" Production casing cemented on bottom with 100 Sx. Top perforations @

3534'. Hole in 5 1/2" @ approximately 3000'. 5 1/2" casing has been squeezed in Dakota.

Squeezed 5 1/2" casing initially with 1 sacks hulls, and 25 Cu. Ft. cement then 30 sacks

gel to 925' and finally 125 Cu. Ft. cement from 925' to bottom of cellar. Maximum

pump-in pressure- 600#. Final shut-in pressure 250#. Squeezed annulus with 150 Cu.

Ft. cement from 900' to bottom of cellar. (Mudding and cementing operations by Allied

Cementing Co., Inc.).

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: *W. J. Deleh*  
Well Plugging Supervisor

DATE 3-23-73  
INV. NO. 7165-W