

KANSAS

**STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT**

**RECEIVED
STATE CORPORATION COMMISSION
3-23-1973
MAR 23 1973
CONSERVATION DIVISION
Wichita, Kansas**

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name John O. Farmer, Incorporated,
Complete Address 370 West Wichita Avenue, Russell, Kansas.
Lease Name DeYoung Well No. C-1
Location NW-NW-SE Sec. 11 Twp. 10 Rge. (E) (W) 21
County Graham Total Depth 3782'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated _____
Plugging Contractor Above
Address _____ License No. _____
Operation Completed: Hour 3:00 PM Day 19 Month 3 Year 1973

The above well was plugged as follows:

165'--8 5/8" Surface casing, cement circulated with 100 Sx.
3777'-5 1/2" Production casing cemented on bottom with 100 Sx. Well plugged back to 3765'. Top of perforations from 3491' to 3495'. 5 1/2" has been squeezed from Dakotas to surface with cement.

Squeezed 5 1/2" casing initially with 25 Cu. Ft. cement then 30 sacks gel and finally 125 Cu. Ft. cement from 925' to bottom of cellar. Maximum pump-in pressure--600#.
Final shut-in pressure-200#. (Mudding and cementing operations by Allied Cementing Company, Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *H. L. Dehols*
Well Plugging Supervisor

DATE 3-23-73

INV. NO. 7159-W