

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
12-11-1967  
DEC 11 1967  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name John O. Farmer, Incorporated.

Complete Address Box #352, Russell, Kansas.

Lease Name Miller Well No. 5

Location SE-NE-NW Sec. 11 Twp. 10 Rge. (E) (W)21

County Graham Total Depth 4226'

Abandoned Oil Well          Gas Well          Input Well          SWD Well X D & A         

Other well as hereafter indicated         

Plugging Contractor Allied Cementing Company, Incorporated.

Address Box #207, Russell, Kansas. License No.         

Operation Completed: Hour 10:00 AM Day 6 Month 12 Year 1967

The above well was plugged as follows:

150'--8 5/8" Surface pipe, cement circulated with 125 Sx.

3939'--5 1/2" casing cemented on bottom with 150 Sx. DV Tool set @ 1700' with cement to surface. Approximately 3000' tubing left in hole.

Squeezed 5 1/2" with 19 sacks gel followed with 35 Sx. cement from 1350' to 900' then

5 sacks gel from 900' to 200' when 10 Sx. cement from 200' to 120', 1 sack gel from

120' to 40' and 5 Sx. cement from 40' to cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Orshel  
Well Plugging Supervisor

DATE 12/12/67  
INV. NO. 6883-W