

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1971
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ralph Comstock of Ralph Comstock Csg. Pulling, has this date requested permission to plug the following described well:Mr. Comstock guarantees payment of the plugging fee.Operator's full Name: John O. Farmer, Incorporated,Complete Address: Box #352, Russell, Kansas.Lease Name: Dietz Waterflood Well No. 2 (Dietz #2)Location: N/2-N/2-S# Sec. 8 Twp. 10 Rge. (E)(W) 23County: Graham Total Depth 3995' Oil Well XGas Well Input Well SWD Well D & A Lost Hole Mr. Comstock was instructed to plug the well as follows:180'--8 5/8" Surface casing, cement circulated.3995'--5 1/2" Production casing cemented on bottom. Top perforations @ 3900'.Push plug to 3700', sand back to 3675' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 170 Sx. cement, staged.

Very truly yours,

Conservation Division Agent