

15-065-20084-0000

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 21 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Paul Stevens of Omega Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Stevens guarantees payment of the plugging fee.

Operator's full Name: Beacon Resources Corpt. & Alpha Oil Co. Inc.,

Complete Address: 412 Union Center, Wichita, Kansas.

Lease Name: Titus Denning Well No. 1

Location: SW-SE-NE Sec. 2 Twp. 10 Rge. (E)(W) 23

County Graham Total Depth 3488 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Stevens was instructed to plug the well as follows:

200'--8 5/8" Surface pipe, cement circulated with 165 Sx.
Dakota section from 1390' to 1185'.

Circulate hole with heavy mud. Pull DP to 1407' and displace 100 Sx.
cement thru DP. Pull DP to 210' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent