

State of Kansas



WM. H. AVERY Governor  
 WILLIAM L. MITCHELL Chairman  
 JOHN C. WOELK Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV 21 1966  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita 2, Kansas

Dear Sir:

Mr. A. J. Burke of March Drilling Co. Inc., has this date requested permission to plug the following described well:

Mr. Burke guarantees payment of the plugging fee.

Operator's full Name: March Drilling Company, Incorporated.

Complete Address: P.O. Box #463, Hutchinson, Kansas.

Lease Name: Dietz Well No. 1

Location: CW/2-W/2-NW/4 Sec. 8 Twp. 10 Rge. (E)(W)23

County Graham Total Depth 4000 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Burke was instructed to plug the well as follows:

204'--8 5/8" Surface pipe, cement circulated with 160 Sx.  
4000'--5 1/4" casing cemented on bottom. 2" tubing in well at  
start of plugging operations.

Displace 10 Sx. gel followed by 25 Sx. cement on bottom thru  
tubing. Pull 5 1/2" tubing to 700' and circulate heavy gel mud  
then displace 10 Sx. cement thru tubing @ 700'. Pull tubing  
to 210' and displace 10 Sx. cement thru tubing. Pull tubing  
set bridge @ 35' and 5 Sx. cement to bottom of cellar.

Very truly yours,

A. L. Nichols  
 Conservation Division Agent