

15-065-03059-0000 *SP*

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ralph Comstock of Ralph Comstock Csg. Pulling has this date requested permission to plug the following described well:

Mr. Comstock guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: Box #352, Russell, Kansas.

Lease Name: Dietz Waterflood Well No. 3 (Dietz B-3)

Location: SE-SW-NW Sec. 8 Twp. 10 Rge. (E)(W) 23

County: Graham Total Depth 3980' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Comstock was instructed to plug the well as follows:

210'--8 5/8" Surface casing, cement circulated.

3978'--5 1/2" Production casing cemented on bottom with 125 Sx. No plug back indicated. Top perforations @ 3940'.

Push plug to 3700', sand well back to 3675' and set 8 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 170 Sx. cement, staged.

Very truly yours,

H. L. Nichols
Conservation Division Agent