



State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ralph Comstock of Ralph Comstock Casing Pulling has this date requested permission to plug the following described well:

Mr. Comstock guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: Box #352, Russell, Kansas.

Lease Name: Dietz Waterflood Well No. 3-R (Law #1)

Location: W/2-W/2-NE Sec. 8 Twp. 10 Rge. (E)(W) 23

County: Graham Total Depth 3950' Oil Well RTKCC

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Comstock was instructed to plug the well as follows:

207'--8 5/8" Surface casing, cement circulated.
3949'--5 1/2" casing cemented on bottom. Top perforations @ 3918'. 5 1/2" casing has been squeezed in the Dakota with an undetermined amount of cement. No attempt to recover 5 1/2".

Squeeze 5 1/2" casing with 5 sacks hulls, 30 sacks gel and 90 Sx. cement, staged.

Very truly yours,

Conservation Division Agent