



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JUN 11 1965

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Russell Hoberecht of Ace Pipe Pulling Co., has this

date requested permission to plug the following described well:
Murfin Drilling Co.

Mr. Hoberecht guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company,

Complete Address: 617 Union Center, Wichita, Kansas.

Lease Name: Diebolt Well No. 2

Location: SE-NW-NW Sec. 14 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth 3885 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Hoberecht was instructed to plug the well as follows:

224' -- 8 5/8" Surface pipe, cement circulated with 160 Sx.
3885' -- 5 1/2" Production casing cemented with 100 Sx. Well plugged
back to 3735'. Top perforations @ 3703'.

Sand well back to 3690' and set 5 Sx. cement with dump bailer.
Pull 5 1/2" to 600' and circulate heavy gel mud. Pull 5 1/2" to 540'
and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" to 210' and dis-
place 20 Sx. cement thru 5 1/2". Pull 5 1/2", set bridge @ 35' and
10 Sx. cement to bottom of cellar.

Very truly yours,

W. L. Dechule
 Conservation Division Agent