

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

#### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

*PCWP  
KCC  
09-22-67*

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Albert Unruh of Southwest Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Skelly Oil Co.

Complete Address: 1860 Lincoln St., Denver Colorado.

Lease Name: Frank Law Well No. 1

Location: NE-NE-NE Sec. 15 Twp. 10 Rge. (E)(W) 23

County Graham Total Depth 3914 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Unruh was instructed to plug the well as follows:

242'--8 5/8" Surface pipe, cement circulated with 165 Sx.  
3949'--5 1/2" Production casing cemented with 200 Sx. Well Plugged back to 3914'  
Top perforations @ 3695' to 3697'. Stage collar set @ 3367' with Oil to surface.  
Sand well back to 3675' and set 5 Sx. cement with dump bailer. Pull 5 1/2"  
and squeeze well with 35 sacks gel plus 5 sacks hulls and 130 Sx. cement.

Very truly yours,

*H. L. Nichols*  
Conservation Division Agent