

15-065-02293-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Graham County. Sec. 12 Twp 10S Rge. (E)-23 (W)
Location as "NE/CNW&SW&" or footage from lines NW NW SE
Lease Owner Continental Oil Company
Lease Name E. P. Irwin Well No. 1
Office Address Box 161, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4-21 1955
Application for plugging filed 4-21 1955
Application for plugging approved 4-21 1955
Plugging commenced 4-15 1955
Plugging completed 4-21 1955
Reason for abandonment of well or producing formation noncommercial

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production --- 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation None Depth to top --- Bottom --- Total Depth of Well 4185 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	202.37'	
				5 1/2	4221.83'	2924.27'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from --- feet to --- feet for each plug set.

Plugging started 4-15-55 and completed 4-21-55. Spudded out bridge and plugged back to 4050' with crushed rock and dumped 5 sacks of cement. Shot casing off at 2918' and pulled pipe out of hole. Filled hole with heavy mud, set permanent rock bridge at 200', and dumped in 20 sacks of cement. Cap on well with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J. O. Forbes - Forbes Casing Pulling Company
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
E. P. Irwin (employee of owner) or (~~owner~~ operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 161, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of May, 1955

My commission expires Dec. 4, 1958

Verdella M. Jenkins
Notary Public.

PLUGGING
FILE SEC 12 T 10 R 23W
BOOK PAGE 114 LINE 15

MAY 20 1955
CONSERVATION DIVISION
Wichita, Kansas
05-30-55

CERTIFIED DRILLER'S LOG

COMPANY: CONTINENTAL OIL COMPANY LEASE: E. P. IRWIN #1
 CONTRACTOR: H & H DRILLING COMPANY LOCATION: NW NW SE
 COMMENCED: 3-8-55 Section 12-10-23W
 GRAHAM COUNTY, KANSAS
 COMPLETED: 3-22-55 CASING RECORD:
 199' of 8-5/8", cem. w/125 sacks.
 4185' of 5-1/2", cem. w/250 sacks.
 ELEVATION:
 POTENTIAL:

<u>FORMATION</u>	<u>DEPTH</u>
Clay, Sand & Shale	0 -- 202
Clay & Shale	202 --- 575
Shale and Sand	575 -- 1265
Shale & Lime	1265 -- 1442
Sand	1442 -- 1632
Shale	1632 -- 1932
Anhydrite	1932 -- 1985
Shale & Shells	1985 --- 2445
Shale & Lime Streaks	2445 -- 2590
Shale & Lime	2590 -- 3111
Lime	3111 -- 3352
Shale & Lime	3352 -- 3568
Lime	3568 -- 4019
Shale & Lime	4019 -- 4086
Lime & Chert	4086 -- 4105
Chert	4105 -- 4172
Lime	4172 -- 4185
RTD	4185 --

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

/s/ R. E. Hartman
 R. E. Hartman

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 24th day of March, 1955.

/s/ Ella Priess
 Notary Public

My Commission Expires: August 25, 1956.

SCC RFD SRC FLD

RECEIVED
 DIVISION
 07-19-55

PLUGGING
 FILE SEC 12 T 10 R 23W
 BOOK PAGE 114 LINE 15