


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Graham County. Sec. 14 Twp. 10 Rge. (E) 23 (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE NE  
Lease Owner Harry Gore  
Lease Name Walker Well No. 1  
Office Address 400 Brown Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 4-1-51 19  
Application for plugging filed 4-1-51 19  
Application for plugging approved 4-1-51 19  
Plugging commenced 4-1-51 19  
Plugging completed 4-1-51 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty Hays, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4284 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	200'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud from 4284 to 200' plug at 200' and 15 sacks of cement and  $\frac{1}{2}$  sack of cotton seed hulls. Top plug at 40' with 10 sacks of cement and  $\frac{1}{2}$  sack of cotton seed hulls.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 11 1951 04-11-51  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Harry Gore  
Address 400 Brown Building  
Wichita, Kansas

STATE OF KANSAS, COUNTY OF MONTGOMERY, ss.  
FLOYD W. HILD (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) THE VEEDER SUPPLY & DEVELOPMENT COMPANY  
Floyd W. Hild

P. O. Box 201, Cherryvale, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 7th day of April, 1951

Leo Lawson  
Notary Public.


My commission expires July 11, 1952

PLUGGING  
FILE SEC 14 T 10 R 25  
BOOK PAGE 71 LINE 1



15-065-00193-0000

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Drilled for Harry Gore Farm Walker No. 1 Depth 4284'  
 Contractor The Veeder Supply & Development Company Pipe Set 213' of 8-5/8" Casing Cemented with 125 sacks  
 Location NE/4 Sec. 14 Twp. 10 Range 23  
 Commenced 3-17-51 Completed 4-1-51 County Graham State Kansas

Surface Soil	0	30	30
Sand Clay	30	90	60
Sand Shale Shells	90	140	50
Shale	140	215	75
Shale Shells	215	910	695
Sand	910	985	75
Shale Shells	985	1370	385
Sand Shale	1370	1700	330
Shale Shells	1700	1815	115
Shale Shells Red Bed	1815	1850	35
Anhydrite	1850	1995	145
Shale Shells	1995	2320	325
Lime Shale Iron	2320	3140	820
Lime	3140	3175	35
Lime Shale	3175	3605	430
Lime	3605	3675	70
Lime Shale	3675	3705	30
Lime	3705	3921	216
Lime Shale	3921	4063	142
Lime Cherty	4063	4081	18
Lime Shale	4081	4160	79
Conglomerate	4160	4210	50
Lime Shale	4210	4247	37
Lime	4247	4284	37
Total Depth	4284'		

Tops:

Topeka	3463
Heebner Shale	3681
Brown Lime	3703
Lansing K.C.	3717
Base K.C.	3949
Cherty Conglomerate	4136
Arbuckle Chert	4247
Arbuckle Dolomite	4251

Plugged: Bottom plug 200' with 70 sacks cement. Top plug 40' with 10 sacks cement.

AFFIDAVIT

STATE OF KANSAS )  
 MONTGOMERY COUNTY ) SS:

FLOYD W. HILD, of lawful age, being duly and solemnly sworn on oath says; I am a resident of Cherryvale, Montgomery County, Kansas, and I hereby know and on oath state, that the above drilling log covering the Walker #1 Well in Section 14-10-23, Graham County, Kansas, is true and correct. Further affianth saith not.

THE VEEDER SUPPLY & DEVELOPMENT COMPANY

By Floyd W. Hild

Subscribed and sworn to before me this 4th day of April, 1951.

Leo L. Linn  
 Notary Public

My Commission Expires: July 11, 1952.

**PLUGGING**  
 FILE SEC 14 T 10 R 23  
 BOOK PAGE 24 LINE 1