

RECEIVED
MAY 30 2003
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME IRWIN (LAW UNIT)

WELL NUMBER 3

4950 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 12 TWP. 10 RGE. 23 (E) or (W)

COUNTY GRAHAM

Date Well Completed 8-29-55

Plugging Commenced 5-15-2003

Plugging Completed 5-15-2003

LEASE OPERATOR GLM CO.

ADDRESS P.O. BOX 193, RUSSELL, KS. 67665

PHONE# (785) 483 2123 OPERATORS LICENSE NO. 3134

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-14-2003 (date)

by CASE MORRIS (KCC District Agent's Name)

Is ACO-1 filed? NO If not, is well log attached? NO

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		166'	0'	8 5/8"		NONE
		4122'	0'	5 1/2"		NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s.
PERF 2 HOLES @ 2575', 1975', 1100'. RUN TBG. TO 3650' MIX 100SKS & 300# HULLS, PULL TBG. TO 3000' MIX 11 SKS GELL & 200# HULLS, PULL TBG. TO 2500', MIX 75 SKS & 100# HULLS, pull TBG. TO 1100', MIX 80 SKS & 100# HULLS, CIRC. CEMENT TO SURFACE. PULL OUT W/TBG. FILL CSG. W/50 SKS. TIE ON TO BRADENHEAD PSI TO 300# ALL CEMENT 60-40POZ 10% GELL

Name of Plugging Contractor ALLIED CEMENTING License No. _____

Address 24 S. LINCOLN, RUSSELL, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: GLM CO.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

TERRY E. MORRIS ~~Blank XXXXX Operator~~ or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Terry E. Morris


(Address) PO Box 193 RUSSELL KS 67665

SUBSCRIBED AND SWORN TO before me this 28th day of May, 2003

Lita M. Clenney
Notary Public

My Commission Expires: December 17, 2003

USE ONLY ONE SIDE OF EACH FORM


RITA M. CLENNEY
Notary Public - State of Kansas
My Appt. Exp. 12/17/2003