


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Graham County, Sec. 15 Twp. 10S Rge. 23W (E) (W)
Location as "NE/CNW'SW" or footage from lines NW NW NW
Lease Owner Imperial Oil of Kansas, Inc.
Lease Name Law Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 3, 1955
Application for plugging filed October 11, 1955
Application for plugging approved October 11, 1955
Plugging commenced October 23, 1955
Plugging completed October 23, 1955
Reason for abandonment of well or producing formation No production
If a producing well is abandoned, date of last production September, 1955
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation Lansing Depth to top 3704' Bottom Total Depth of Well 3955 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"		← 258'
				5-1/2"		← 3955' 2800'

RT
KCC

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.


Plugged back with crushed rock from 3931' to 3885'. Dumped 4 sacks cement at 3885' with dump bailer. Top of cement, 3860'. Filled hole with mud to 220', set rock bridge, dumped 15 sacks cement. Top of cement, 175'. Filled with mud to 35', set rock bridge, dumped 10 sacks cement for cap.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Miller Casing Plugging Company
Address Post Office Box 711, Great Bend, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK ss.
Raymond L. Bacon (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God IMPERIAL OIL OF KANSAS, INC.

(Signature) By: Raymond L. Bacon V-P
903 Union National Bank Bldg.
Wichita, Kansas
(Address)



SUBSCRIBED AND SWORN to before me this 3rd day of November, 1955

Francis E. Bailean Notary Public.

PLUGGING
FILE SEC 15 T 10 R 23 W
BOOK PAGE 2 LINE 22

RECEIVED
STATE CORPORATION COMMISSION
NOV - 4 1955 11-04-55
CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S LOG

Imperial Drilling Company, Inc.
903 Union National Bank Building
Wichita, Kansas

Frank Law No. 1
NW NW NW Sec. 15-10S-23W
Graham County, Kansas

Total Depth: 3955'

Commenced: February 14, 1955 Completed: February 25, 1955

Elevation: 2408' R.B.
Production: 27 BOPD
69% water

Contractor: Imperial Drilling Company, Inc.
Wichita, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 258' W/155 sacks cement.
Set 5-1/2" casing at 3955' W/125 sacks cement.

Figures indicate bottom of formation:

Surface Clay, Sand and Rock	258'		
Clay and Shale	280'		
Shell and Shells	985'		
Hard Sand and Shale	1385'		
Shale and Shells	1500'		
Dakota Sand	1710'		
Shale and Shells	1963'		
Anhydrite	2005'		
Shell and Shells	2490'		
Lime and Shale	3562'		
Lime	3955'		
Rotary Total Depth	3955'		
		<u>TOPS</u>	
		Anhydrite	1963' (445)
		Heebner	3670' (-1262)
		Lansing	3704' (-1296)
		Rotary Total Depth	3955' (-1547)

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling report.

IMPERIAL DRILLING COMPANY, INC.

By: Ray E. Bacon
Vice-President

Subscribed and sworn to before me this 25th day of March, 1955.

My commission expires:
November 9, 1957

Marion E. Fox
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
OCT 12 1955
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FLX SEC 15 T-10 R226
BOOK PAGE 2 LINE 32