

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

WELL PLUGGING RECORD

15-195-20382-00-00

Give All Information Completely
 Make Required Affidavit

COUNTY Trego SEC. 7 TWP. 12S RGE. 22W E/W
 Location as in quarters or footage from lines:
 NW NW

Lease Owner Moble C. Hoover
 Lease Name D.C. Newcomer #1 Well No. _____
 Office Address 302 NBC Building ElDorado, Arkansas 71730
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 6-17-82
 Plugging completed 8-12-82
 Reason for abandonment of well or producing formation _____
 Depleted

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel

Producing formation _____ Depth to top _____ bottom T.D. 3905'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	243'	none
				4-1/2"	3901'	2234'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Ran 1 barrel of sand and 4 sacks of cement and pushed bottom plug to 3800'. Shot casing
 @3115', 2993', 2870', 2747', 2500', 2383' and 2245'. Pulled a total of 72 joints of
 4-1/2" casing. Washed 2" tubing to 1050' pumped 3 sacks gel, 1 sack hulls, and
 displaced; pulled tubing to 900', pumped 70 sacks 50/50 pos, 4% gel, 3% cc; pulled
 tubing to 600', pumped 9 sacks gel and displaced; pulled tubing to 280' and pumped
 70 sacks cement, 50/50 pos, 4% gel, 3% cc.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.


R. Darrell Kelso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso

Box 347 Chase, Kansas 67524
 (Address)



SUBSCRIBED AND SWORN TO before me this 17th day of August, 19 82



Irene Hoover
 Notary Public.

My Commission expires: