


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-195-00301-00-00  
WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

TREGO County. Sec. 7 Twp. 12S Rge. 22W (E) (W)

Location as "NE/CNW%SW%" or footage from lines NW SW SW  
Lease Owner K & E DRILLING, INC.  
Lease Name NEWCOMER Well No. 1  
Office Address 719 Union Center Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 7-28-57 19  
Application for plugging filed 7-28-57 19  
Application for plugging approved 7-28-57 19  
Plugging commenced 7-28-57 19  
Plugging completed 7-28-57 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Brundage  
Producing formation Depth to top Bottom Total Depth of Well 3910 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	251'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill with heavy mud to 750' & set plug and solid bridge.  
Cement with 25 sacks common cement thru drill pipe. Fill with heavy mud to 240'. Set solid plug and bridge with 1/2 sack hulls and 15 sacks common cement. Fill with heavy mud to 40'. Set solid bridge. Cement with 10 sacks cement. Plugging complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor K & E DRILLING, INC.  
Address 719 Union Center Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Dale Silcott (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Silcott  
Dale Silcott of K & E DRILLING, INC.  
719 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of August, 19 57

My commission expires 11 August 1958.

RECEIVED  
Patricia M. Edwards  
STATE CORPORATION COMMISSION  
Notary Public.

PLUGGING  
FILE SEC 7 T 12 R 22W  
BOOK PAGE 32 LINE 32

AUG 3 1957  
08-03-1957  
CONSERVATION DIVISION  
Wichita, Kansas

15-195-00301-00-00

WELL LOG

OPERATOR:	K & E DRILLING, INC. 719 Union Center Building Wichita 2, Kansas	FARM NAME:	#1 NEWCOMER
CONTR:	K & E DRILLING, INC. 719 Union Center Building Wichita, Kansas	LOCATION:	NW SW SW Sec. 7-12S-22W Trego County Kansas
CASING:	8-5/8" @ 251 (160 sx)	COMMENCED:	7-20-57
R.T.D.	3910'	COMPLETED:	7-28-57
		ELEVATION:	2386' KB

FORMATION RECORD

Depths shown indicate bottom of formations encountered

Shaleq	45
Sand	120
Shale	690
Sand	950
Iron & Sand	1050
Shale	1260
Sand & Shale	1545
Red Bed & Shale	1770
Red Bed	1800
Anhydrite	1845
Shale & Shells	2060
Shells & Shale	2340
Lime & Shale	2485
Lime & Shale	2675
Lime	2770
Sandy Lime	2930
Lime & Shale	3010
Shale	3065
Lime	3110
Lime & Shale	3355
Lime	3485
Lime & Shale	3555
Lime	3621
Shale	3625
Lime & Shale	3710
Lime	3880
Lime & Shale	3910
R.T.D.	3910

CERTIFICATION

STATE OF KANSAS )  
 ) SS:  
 COUNTY OF SEDGWICK )


I, Dale Silcott of the K & E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the log of our #1 NEWCOMER well.

*Dale Silcott*  
 \_\_\_\_\_  
 Dale Silcott

Subscribed and sworn to before me this 1st day of August 1957

*Patricia M Edwards*  
 \_\_\_\_\_  
 Patricia M Edwards, Notary Public

My commission expires: 11 August 1958.



EXPIRES  
 STATE COMMISSION

PLUGGING  
 FILE SEC 1 T 12 R 22W  
 BOOK PAGE 32 L E 32

AUG 31 7  
 08-03-1957  
 COMMISSION EXPIRES