

15-195-20883-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

Rec'd
10-16-81

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Trego SEC. 6 TWP. 12S RGE. 22W E/W
Location as in quarters or footage from lines:
1650 FWL 990 FSL SW/4

Lease Owner Moble C. Hoover
Lease Name JUDY RINKER Well No. 1
Office Address 302 NBC Bldg., El Dorado, Ark, 71730
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed 10/10/81
Application for plugging filed 10/10/81
Plugging commenced 10/10/81
Plugging completed 10/10/81

Locate Well
correctly on above
Section Platt.

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazar
Producing formation _____ Depth to top _____ bottom _____ T.D. 4135'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Set 1st plug @ 900' with 70 sx.
Set 2nd plug @ 280' with 40 sx.
Set 3rd plug @ 40' Solid Bridge with 10 sx.
Plug was down @ 10:15 p.m., 10/10/81

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Vice Pres. (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of October, 19 81

My Commission expires: 7-13-85

Elizabeth G. Terry
Elizabeth G. Terry Notary Public


State

Recd
10-16-81

15-195-20883-00-00

CONTRACTORS WELL LOG

OPERATOR: Moble C. Hoover
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: JUDY RINKER #1
 LOCATION: 1650 FWL 990 FSL SW/4
 Trego County, Kansas
 SPUD DATE: 10/01/81
 COMPLETION DATE: 10/10/81

0	1834	Sand & Shale
1834	1873	Anhydrite
1873	2355	Shale & Sand
2355	2548	Sand, Shale & Lime
2548	4135	Shale & Lime
	4135	Rotary Total Depth

Spud hole @ 12:15 p.m., 10/01/81. Drilled 285' of a 12 1/2" hole. Ran 7 jts. of 8 5/8" 20# casing set @ 283.96' and cemented with 185 sx. Common 2% gel, 3% c.c. Cement did circulate. Plug was down @ 6:00 p.m., 10/01/81.

4135' TD. 4141' LTD. Set 1st plug @ 900' with 70 sx. Set 2nd plug @ 280' with 40 sx. Set 3rd plug @ 40' Solid Bridge with 10 sx. 10 sx. in Rathole. 50-50 posmix, 6% gel. Plug was down @ 10:15 p.m., 10/10/81.

SAMPLE TOPS:

Anhydrite 1835'
 B/Anhydrite 1873'
 Heebner 3632' (-1218)
 Toronto 3654' (-1240)
 Lansing 3668' (-1254)

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the JUDY RINKER #1, 1650 FWL 990 FSL SW/4, Sec. 6-12S-22W, Trego County, KS.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Vice Pres.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 14th day of October, 1981.

Elizabeth G. Terry
 Elizabeth G. Terry
 NOTARY PUBLIC

my commission expires 7-13-85

