


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Trego County, Sec. 6 Twp. 12S Rge. 22WE/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
C NW NE NE

Lease Owner Moble C. Hoover  
Lease Name Newcomer Well No. 1-B  
Office Address 302 NBC Bldg., El Dorado Arkansas  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole



Locate well correctly on above  
Section Plat

Date Well completed Dec 13 19 78  
Application for plugging filed (verbally) Dec 13 19 78  
Application for plugging approved (verbally) Dec 13 19 78  
Plugging commenced Dec 13 19 78  
Plugging completed Dec 13 19 78  
Reason for abandonment of well or producing formation  
No commercial quantity of oil or gas encountered  
If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3930'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

T.D. 3930'  
Set 1st plug at 950' with 70 sacks  
2nd plug at 240' with 20 sacks  
3rd plug at 40' solid bridge with 10 sacks  
Cemented with 50/50 posmix, 6% gel.  
Plug was down at 9:00 a.m., December 13, 1978.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 21 1978  
12-21-1978  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. --So help me God.



(Signature) Jack L. Partridge  
801 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of December, 19 78

Sherrie L. Brooks  
Sherrie L. Brooks Notary Public.

My commission expires August 21, 1982.

OPERATOR: Moble C. Hoover  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: Newcomer #1-B  
 LOCATION: C NW NE NE, Section 6-12S-22W  
 Trego County; Kansas  
 SPUD DATE: December 4, 1978  
 COMPLETION DATE: December 13, 1978

0	779	Sand and shale
779	998	Sand
998	1648	Sand and shale
1648	1810	Shale and sand
1810	2787	Shale
2787	3452	Shale and lime
3452	3615	Lime and shale
3615	3690	Shale and lime
3690	3878	Lime
3878	3930	Lime and shale
	3930	Rotary Total Depth

Spud hole at 5:45 p.m., December 4, 1978. Drilled 266' of 12 1/4" hole. Ran 6 joints of 8 5/8" - 28# casing. Set at 264' K.B. with 160 sacks of sun cement. Cement did not circulate. Plug was down at 1:30 a.m., December 5, 1978.

T.D. 3930'. Set 1st plug at 950' with 70 sacks, 2nd plug at 240' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 9:00 a.m., December 13, 1978.

SAMPLE TOPS:

Anhydrite 1857'  
 B/Anhydrite 1907'

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 21 1978  
 12-21-1978  
 CONSERVATION DIVISION  
 Wichita, Kansas


STATE OF KANSAS )  
 ) ss  
 COUNTY OF SEDGWICK )

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Newcomer #1-B C NW NE NE, Section 6-12S-22W, Trego County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge  
 Jack L. Partridge  
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 19th day of December, 1978.



Sherrie L. Brooks  
 Sherrie Brooks, Notary Public

My commission expires 8-21-82.