



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

JAN 6 1971

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. D. J. Iannitti of Woodman-Iannitti Oil Company has this date requested permission to plug the following described well:

Mr. Iannitti guarantees payment of the plugging fee.

Operator's full Name: Woodman-Iannitti Oil Company,

Complete Address: 706 Union National Bank Building, Wichita, Kansas.

Lease Name: Faulkner Well No. 2

Location: CN/2-NW-NW Sec. 22 Twp. 10 Rge. (E)(W) 22

County: Graham Total Depth 3800' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Iannitti was instructed to plug the well as follows:

139'--8 5/8" Surface casing, cement circulated with 100 Sx.
3785'--5 1/2" Production casing cemented on bottom with 100 Sx. Well
plugged back to 3768'. Top perforations @ 3702'.

Squeeze 5 1/2" casing with 1 sack hulls, 31 sacks gel and 105 Sx. cement,
staged. Squeeze annulus with 4 sacks hulls, 7 sacks gel and 35 Sx. cement,
staged.

Very truly yours,

M. L. Nichols
Conservation Division Agent