

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ST. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 11 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Dwight Delenger of Knight Casing Pulling Co has this date requested permission to plug the following described well:

Mr. Dellenger guarantees payment of the plugging fee.

Operator's full Name: Ralph A. Comeau,

Complete Address: 311 So. Jefferson, Plainville, Kansas.

Lease Name: McCall Well No. D-2

Location: SE-NW-NW Sec. 31 Twp. 10 Rge. (E) (W) 22

County Graham Total Depth 4130 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Delenger was instructed to plug the well as follows:

213'--8 5/8" Surface pipe, cement circulated with 150 Sx.
4130'--5 1/2" Production casing cemented with 150 Sx. D. V. Tool
@ 1797'-- Cemented to surface. Top perforations @ 3530' to 3538'.

Push plug to 3500'. sand back to 3475' and set 5 Sx. cement with
dump bailer. Find top of fluid & build rock bridge and fill to
bottom of cellar with Redi-Mix.

Very truly yours,

H. A. Ziebel
Conservation Division Agent