

State of Kansas



JOHN ANDERSON, Jr. Governor
 WILLIAM L. MITCHELL, Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 W. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JAN 11 1965

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Dwight Delenger of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Delenger guarantees payment of the plugging fee.

Operator's full Name: Ralph A. Comeau,

Complete Address: 311 So. Jefferson, Plainville, Kansas.

Lease Name: McCall Well No. D-1

Location: NW-NW-NW Sec. 31 Twp. 10 Rge. (E) (W) 22

County Graham Total Depth 3767 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Delenger was instructed to plug the well as follows:

216' -- 8 5/8" Surface pipe, cement circulated with 135 Sx.
3767' -- 5 1/2" Production casing cemented with 75 Sx. 5 1/2" squeezed
in the Dakotas. Top perforations from 3539' to 3545'.

Sand well back to 3400' and set 5 Sx. cement with dump bailer.
Find top of fluid, set rock bridge and fill to bottom of cellar
with Redi-Mix.

Very truly yours,

Conservation Division Agent