

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
MONT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 5 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Dwight Dellenger of Knight Casing Pulling Co. has this

date requested permission to plug the following described well:

R. A. Comeau
Mr. Dellenger guarantees payment of the plugging fee.

Operator's full Name: Ralph A. Comeau,Complete Address: 311 South Jefferson, Plainville, Kansas.Lease Name: McCall Well No. D-4Location: NW-NE-NW Sec. 31 Twp. 10 Rgs. (E) (W) 22County Graham Total Depth 3848 Oil Well XGas Well Input Well SWD Well D & A Lost Hole Mr. Dellenger was instructed to plug the well as follows:

.220' -- 8 5/8" Surface pipe, cement circulated with 150 Sx.
3848' -- 5 1/2" Production casing cemented with 100 Sx. Top
perforations from 3532 to 3540.

Sand well back to 3520' and set 5 Sx. cement with dump bailer.
Pull 5 1/2", find fluid level, if between 400 & 450' set rock
bridge and fill to bottom of cellar with Redi-Mix cement.

Very truly yours,

W. L. Nichols
Conservation Division Agent