

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
MAR 13 1967

MAR 13 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Lowell Moore of C & G Drilling Company has this  
date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: D. G. Hansen Trust,

Complete Address: Logan, Kansas.

Lease Name: Gano Well No. 10

Location: SW-SW-NW Sec. 6 Twp. 10 Rge. (E)(W) 23

County Graham Total Depth 4010 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Moore was instructed to plug the well as follows:

198'--8 5/8" Surface pipe, cement circulated with 150 Sx.

Circulate hole with heavy mud, set plug @ 540' and 20 Sx. cement.

"	"	210'	with $\frac{1}{2}$ sk. hulls & 20 Sx. cement.
"	"	40'	with $\frac{1}{2}$ sk. hulls & 10 Sx. cement.

Very truly yours,

M. L. Nichols  
Conservation Division Agent