

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 25 1965
07-25-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Moore of C & G Drilling Co. has this date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: Dan G. Hansen Trust

Complete Address: Logan, Kansas

Lease Name: Kerman Well No. 1

Location: NW NW SW Sec. 7 Twp. 10 Rge. 23 (E)(W) X

County Graham Total Depth 4025 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Moore was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540 Ft.
and displace 20 sc cement thru drill pipe. Heavy mud to 180 Ft. set
cementing plug and displace 20 sc cement thru drill pipe. Heavy mud
to 40 Ft. set cementing plug, 1/3 sc hulls and 10 sc cement to base
of celler. Plug rat hole with 2 sc cement.

Very truly yours,

Conservation Division Agent