



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
JUL 19 1971
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ralph Nernberger of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Nernberger guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company,

Complete Address: 617 Union Center Building, Wichita, Kansas.

Lease Name: Kerman Well No. 1

Location: CS/2-S/2-SW Sec. 7 Twp. 10 Rge. (E)(W) 23

County: Graham Total Depth 3825' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Nernberger was instructed to plug the well as follows:

212'--8 5/8" Surface casing; cement circulated with 150 Sx.
Top of Dakota section @ 900'.

Circulate hole with heavy mud. Pull DP to 1125' and displace 100 Sx.
cement thru DP. Pull DP to 245' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent