



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
AUG 27 1973
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Lowell Moore of C & G Drilling Company has this
date requested permission to plug the following described well:Mr. Moore guarantees payment of the plugging fee.Operator's full Name: C & G Drilling Company.Complete Address: 1107 Union National Building, Wichita, Kansas.Lease Name: Gano Well No. 1Location: NW-NW-NW Sec. 7 Twp. 10 Rge. (E)(W) 23County: Graham Total Depth 3875' Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Moore was instructed to plug the well as follows:211'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 675'.Circulate hole with heavy mud. Pull DP to 900' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 240' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

N. L. Nichols
Conservation Division Agent