

15-065-03042-0000

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____
LOCATION SE SE NW
SEC. 36 TWP. 10 RGE. 21

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 6 Lease Lewis

Operator Harry Gore Address Wichita, Kans

Field _____ County Graham

Total Depth 3746 Feet.

Plugging Contractor Barnes & Sons

Plugging Contractor's License No. 9

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 216' circulated with cement - 5 1/2" at 3594' with 100
sax cement behind. P.B. to 3485', perforations at 3453'.
Filled with sand to 3440', set 4 sax cement with dump bailer,
pulled 2960' 5 1/2" - pumped hole full mud and Gel - pumped cementing
plug to 325' followed by 105 sax cement - cement 325' to 0'.
Mudding and Cementing by Halliburton Cementing - 300# pump pressure.

E. W. Petty
District Conservation Agent

Date 3-15-57

PLUGGING
FILE SEC 36 T. 10 R. 21W
BOOK PAGE 147 LINE 21

RECORDED
STATE CORPORATION COMMISSION
MAR 20 1957
3-29-57
CONSERVATION DIVISION
Wichita, Kansas