

15-065-20566-0000

Form CP-3  
Rev. 6-4-68

KANSAS

*Y*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 7 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Herndon Drilling Company,  
Complete Address Box #489, Tulsa, Oklahoma.  
Lease Name Holmquist Well No. 1  
Location CW/2-SW-NW Sec. 11 Twp. 10 Rge. (E) (W) 22  
County Graham Total Depth 3738'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor B & B Drilling, Incorporated,  
Address 720 Union Center, Wichita, Kansas. License No.         
Operation Completed: Hour 6:30 AM Day 4 Month 9 Year 1972

The above well was plugged as follows:

217'---8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 575'.

Circulated hole with heavy mud. Pulled DP to 800' and displaced 110 Cu. Ft. cement  
thru DP from 800' to 475'. Pulled DP to 220' and displaced 30 Cu. Ft. cement thru DP  
from 220' to 145'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *A. L. Dichek*  
Well Plugging Supervisor

INVOICED

DATE 9/9/72  
INV. NO. 6285-W