

15-065-00614-0000

Form CP-3
Rev. 6-4-68

KANSAS

al

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 6 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Woodman-Iannitti Oil Company,

Complete Address 706 Union National Bank Building, Wichita, Kansas.

Lease Name Faulkner Well No. 1

Location NW-NW-NW Sec. 22 Twp. 10 Rge. (E) (W) 22

County Graham Total Depth 3932'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Sun Oil Well Cementing, Incorporated,

Address Box #69, Hays, Kansas. License No. _____

Operation Completed: Hour 12:30 PM Day 26 Month 12 Year 1970

The above well was plugged as follows:

139'--8 5/8" Surface casing, cement circulated with 90 Sx.
3853'--5 1/2" Production casing cemented on bottom with 100 Sx. Well plugged back to
3836'. Top perforations @ 3744'.
Squeezed 5 1/2" casing with 1 sack hulls and 25 Sx. cement from 3800' to 3700' then 28
sacks gel from 3700' to 950' and followed with 50 Sx. cement from 950' to 550' then
3 sacks gel from 550' to 250' and finally 30 Sx. cement from 250' to bottom of cellar.
Squeezed annulus initially with 4 sacks hulls then 7 sack gel and finally 35 Sx. cement.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 1-6-71

INV. NO. 3156-W