

KANSAS

*2* STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 15 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Petroleum, Incorporated,

Complete Address 300 West Douglas, Wichita, Kansas.

Lease Name Faulkner Well No. M-3

Location App:-CNE-NW Sec. 27 Twp. 10 Rge. (E) (W) 22

County Graham Total Depth 3632'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Garvey Drilling Company,

Address Box #1164, Great Bend, Kansas. License No.       

Operation Completed: Hour 5:00 PM Day 13 Month 7 Year 1971

The above well was plugged as follows:

209'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 775'.

Circulated hole with heavy mud. Pulled DP to 1000' and displaced 100 Sx. cement thru  
DP from 1000' to 675'. Pulled DP to 210' and displaced 25 Sx. cement thru DP from  
210' to 135'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*  
Well Plugging Supervisor

*7/15/71*  
*4001-W*