

DISTRICT CONSERVATION AGENT'S REPORT

TO:

W

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SW-NE-SE

SEC. 29 TWP. 10 RGE. 22 W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. A-2 Lease Faulkner

Operator Wood-River Oil Co Address #355-N-Lewis

Field _____ County Osage

Total Depth 4000 Feet.

(Describe briefly the manner in which the well was plugged)

1800ft of 8 3/8 Surface Pipe in the Hole cemented all around - 5 1/2" casing set at 4000ft & cemented with 300 sacks cement - The well had been plugged back to 3400ft & reformed - Plug & Bridge set in 5 1/2" casing at 2370ft & 10 sacks cement with dump Bailer - 5 1/2" casing then shot off at 2900ft & pulled out - Hole filled with mud to 1800ft - Plug & 10 sacks cement - Mud to 200ft & 10 sacks cement -

Mud to 20ft below the surface & 10 sacks cement filling hole to surface -

Frank Carroll - Pipe Puller

C. H. Stough
District Conservation Agent

Date 7-27-47

PLUGGING
FILE SEC 27 T 10 R 22 W
BOOK PAGE 123 LINE 14

07-31-47

X