

15-065-19212-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 6 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Woodman-Iannitti Oil Company,

Complete Address 706 Union National Bank Building, Wichita, Kansas.

Lease Name Faulkner Well No. 2

Location CN/2-NW-NW Sec. 22 Twp. 10 Rge. (E) (W) 22

County Graham Total Depth 3800'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Sun Oil Well Cementing, Incorporated,

Address Box #69, Hays, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 4:15 PM Day 26 Month 12 Year 1970

The above well was plugged as follows:

139'--8 5/8" Surface casing, cement circulated with 100 Sx.  
3785'--5 1/2" Production casing cemented on bottom with 100 Sx. Well plugged back to 3768'. Top perforations @ 3702'.

Squeezed 5 1/2" casing initially with 1 sack hulls and 25 Sx. cement from 3800' to 3700'  
then 28 sacks gel from 3700' to 950' and followed with 50 Sx. cement from 950' to 550'  
then 3 sacks gel from 550' to 250' and finally 30 Sx. cement from 250' to bottom of  
cellar. Squeezed annulus initially with 4 sacks hulls then 7 sacks gel and finally  
with 35 Sx. cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *K. L. Dickel*  
Well Plugging Supervisor

DATE 1-6-71  
INV. NO. 3157-W