

15-065-20449-0000

Form CP-3  
Rev. 6-4-68

KANSAS

*al*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 2 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Petroleum, Incorporated,  
Complete Address 300 West Douglas, Wichita, Kansas.  
Lease Name Faulkner Well No. N-1  
Location App:CSW-SW Sec. 22 Twp. 10 Rge. (E) (W) 22  
County Graham Total Depth 3640'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Garvey Drilling Company,  
Address 300 West Douglas, Wichita, KANS. License No.         
Operation Completed: Hour 2:15 AM Day 29 Month 5 Year 1971

The above well was plugged as follows:

218'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @775'.  
        
Circulated hole with heavy mud. Pulled DP to 1000' and displaced 100 Sx. cement thru  
DP from 1000' to 675'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from 240'  
to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of  
cellar.  
        
        
      

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*  
Well Plugging Supervisor

INVOICED

DATE 6/2/71  
INV. NO. 3790-W