

15-065-00767-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 11 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Ralph A. Comeau,

Complete Address: 311 South Jefferson, Plainville, Kansas.

Lease Name McCall Well No. D-1

Location NW-NW-NW Sec. 31 Twp. 10 Rge. (E) (W) 22

County Graham Total Depth 3767 ⁴⁰¹⁰ RTKLL

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company,

Address: Box #405, Chase, Kansas. License No. 436

Operation Completed: Hour 4:00PM Day 5 Month 1 Year 1965

The Above well was plugged as follows:

216'--8 5/8" Surface pipe, cement circulated with 135 Sx.
3767'--5 1/2" Production casing cemented with 75 Sx. 5 1/2" squeezed in Dakotas.
Top perforations from 3539' to 3545'.

Sanded well back to 3400' and set 5 Sx. cement with dump bailer.

Hole was mudded off @ 788', set rock bridge @ 788' and filled to bottom
of cellar with 4 1/2 yards 5 to 1 Redi-Mix.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 1-12-65

INV. NO. 508W