

15-065-03049-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 11 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Ralph A. Comeau,

Complete Address: 311 South Jefferson, Plainville, Kansas.

Lease Name McCall Well No. D-2

Location SE-NW-NW Sec. 31 Twp. 10 Rge. (E) (W) 22

County Graham Total Depth 4280
4130 RT_{ALL}

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company,

Address: Box #405, Chase, Kansas. License No. 436

Operation Completed: Hour 2:00PM Day 4 Month 1 Year 1965

The Above well was plugged as follows:

213'--8 5/8" Surface pipe, cement circulated with 150 Sx.
4130'--5 1/2" Production casing cemented with 150 Sx. DV Tool @ 1797'. 5 1/2"
cemented back to surface. Top perforations from 3530' to 3538'.

Pushed plug to 3500', sanded back to 3475' and set 5 Sx. cement with
dump bailer. Found top of fluid @ 1300', build rock bridge and filled
5 1/2" to bottom of cellar with 5 to 1 Redi-Mix using 7 1/2 yards.
(No attempt made to recover 5 1/2" casing)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. Zehle
Well Plugging Supervisor

DATE 1-12-65

INV. NO. 509-W