

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JAN 5 1965
01-05-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Ralph A. Comeau,

Complete Address: 311 South Jefferson, Plainville, Kansas.

Lease Name McCall Well No. D-4

Location NW-NE-NW Sec. 31 Twp. 10 Rge. (E) (W) 22

County Graham Total Depth 3848

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Company,

Address: Box 3405, Chase, Kansas License No. 436

Operation Completed: Hour 1:--PM Day 2 Month 1 Year 1965

The Above well was plugged as follows:

220'--8 5/8" Surface pipe, cement circulated with 150 Sx.

3848'--5 1/2" Production casing cemented with 100 Sx. Top perforations from 3532' to 3540'.

Was unable to get below 2250' with bailer inside 5 1/2" so set bridge @ 2250' and 5 Sx. cement with dump bailer. ~~REMOVED~~ Pulled 5 1/2" casing and bailed hole to 410' where mud bridge was encountered. set 10' rock bridge and 6 yards Redi-Mix to bottom of cellar. (Recovered 1300' 5 1/2" casing)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. Nichols
Well Plugging Supervisor

DATE 1-5-65

INV. NO. 471-W