

15-065-02951-000

Form CP-3
Rev. 6-4-68

KANSAS

24
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JAN 24 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Koch Exploration Company,

Complete Address P. O. Box #2256, Wichita, Kansas.

Lease Name Faulkner Well No. B-1

Location NE-SW-SE Sec. 27 Twp. 10 Rge. (E) (W) 22

County Graham Total Depth 3808'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Halliburton Services,

Address P. O. Box #296, Hill City, Kansas. License No. _____

Operation Completed: Hour 7:00 PM Day 20 Month 1 Year 1972

The above well was plugged as follows:

200'--10 3/4" Surface casing, cement circulated.

1800'--8 5/8" Intermediate String, cement circulated.

3808'--5 1/2" Production casing cemented on bottom. This well was previously plugged and 5 1/2" casing pulled from 715'. Well later washed to 3808' with rotary. Dakota has broken in @ approximately 1050'. Shot hole in 5 1/2" casing @ 2600'.

Attempted to squeeze well with 5 sacks hulls, 30 sacks gel and 170 Cu. Ft. cement. Squeezed with 5 sacks hulls and 18 sacks gel and followed with 100 Cu. Ft. cement, pressure built to 600#, pumped in the additional 70 Cu. Ft. cement slowly and closed well in @ 600#.

I hereby certify that the above well was plugged as herein stated.

Signed: W. S. Nichols
Well Plugging Supervisor

INVOICED

DATE 1-28-72

INV. NO. 5056-W