

15-065-20015-0000

Form CP-3
Rev. 6-26-62

KANSAS

K STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
MAR 13 1967
03-12-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name D. G. Hansen Trust,

Complete Address: Logan, Kansas.

Lease Name Gano Well No. 10

Location SW-SW-NW Sec. 6 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth 4010

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: C & G Drilling Company,

Address: 107 Rule Building, Wichita, Kansas. License No.

Operation Completed: Hour 10:00PM Day 3 Month 3 Year 1967

The Above well was plugged as follows:

198'--8 5/8" Surface pipe, cement circulated with 150 Sx.

Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx.

cement thru DP. Heavy mud to 210', set plug with 1/2 sack hulls and dis-

placed 20 Sx, cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 Sx, cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/13/67

INV. NO. 4893-w

Signed: M. L. Nichols
Well Plugging Supervisor