

15-065-20134-0000

Form CP-3  
Rev. 6-26-62KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, KansasRECEIVED  
STATE CORPORATION COMMISSIONAPR 1 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Dan G. Hansen Trust,

Complete Address: Logan, Kansas. 67646

Lease Name Gano Well No. C-4

Location NE-NE-NW Sec. 7 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth 3970

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: C & G Drilling Company, Incorporated,

Address: 1107 Union National Building, Wichita, Kansas. License No.     

Operation Completed: Hour 1:30 AM Day 27 Month 3 Year 1968

The Above well was plugged as follows:

205'--8 5/8" Surface pipe, cement circulated with 140 Sx.

Top of Dakota section @ 860'.

Circulated hole with heavy mud. Pulled DP to 1100' and displaced 100 Sx. cement thru

DP from 1100' to 775'. Pulled DP to 210' and displaced 20 Sx. cement thru DP from 210'

to 150'. Pulled DP, set bridge @ 40' with  $\frac{1}{2}$  sack hulls and 10 Sx. cement to bottom of

cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

4/1/68

INV. NO.

7497-W

Signed:

H. L. Nichols

Well Plugging Supervisor