

15-065-20627-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 27 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name C. & G Drilling Company,
Complete Address 1107 Union National Building, Wichita, Kansas.
Lease Name Gano Well No. 1
Location NW-NW-NW Sec. 7 Twp. 10 Rge. (E) (W) 23
County Graham Total Depth 3875'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.
Operation Completed: Hour 8:30 PM Day 22 Month 8 Year 1973

The above well was plugged as follows:

211'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 675'.

Circulated hole with heavy mud. Pulled DP to 900' and displaced 110 Cu. Ft. cement thru DP from 900' to 575'. Pulled DP to 240' and displaced 30 Cu. Ft. cement thru DP from 240' to 165'. Pull DP, set bridge @ 40' with $\frac{1}{2}$ sack hulls and 10 Cu. Ft. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/30/73
INV. NO. 7823-42

Signed:

W. L. Nichols
Well Plugging Supervisor