

15-065-19220-0000
PR

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name John O. Farmer, Incorporated.

Complete Address Box #352, Russell, Kansas.

Lease Name Dietz Waterflood Well No. 3-R (Law #1)

Location W/2-W/2-NE Sec. 8 Twp. 10 Rge. (E) (W)23

County Graham Total Depth 3950'

Abandoned Oil Well Gas Well Input Well SWD Well D & A
RTKCC

Other well as hereafter indicated _____

Plugging Contractor Ralph Comstock Casing Pulling, Incorporated.

Address 320 So. Park, Stafford, Kansas. License No. 490

Operation Completed: Hour 2:00 PM Day 3 Month 6 Year 1971

The above well was plugged as follows:

207'--8 5/8" Surface casing, cement circulated.
3949'--5 1/2" casing cemented on bottom. Top perforations @ 3918'. 5 1/2" has been
squeezed in the Dakota with an undetermined amount of cement. No attempt to salvage
5 1/2" casing.

Squeezed 5 1/2" casing initially with 5 sacks hulls and 20 Sx. cement then 27 sacks gel
and followed with 40 Sx. cement then 5 sacks gel and finally 30 Sx. cement. Maximum
pump-in pressure-500#. Final shut-in pressure-200#. Mudding and cementing by Allied).

I hereby certify that the above well was plugged as herein stated.

Signed: R. S. Nichols
Well Plugging Supervisor

INVOICED

DATE 6-10-71

INV. NO. 3838-W