

15-065-20084-0000

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

SEP 21 1967

CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Beacon Resources Corporation & Alpha Oil Company, Incorporated,

Complete Address: 412 Union Center, Wichita, Kansas.

Lease Name Titus Denning Well No. 1

Location SW-SE-NE Sec. 2 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth 3488'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Omega Drilling, Incorporated,

Address: 427 Union Center, Wichita, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 3:00PM Day 16 Month 9 Year 1967

The Above well was plugged as follows:

200'--8 5/8" Surface pipe, cement circulated with 165 Sx.  
Dakota section from 1390' to 1185'.

Circulated hole with heavy mud. Pulled DP to 1407' and displaced 100 Sx. cement thru  
DP from 1407' to 1087'. Pulled DP to 210' and displaced 20 Sx. cement thru DP from 210'  
to 150'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of  
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/21/67  
INV. NO. 6365-W

Signed: W. L. Nichols  
Well Plugging Supervisor